SECTION 8 : BILL OF QUANTITIES

Name of the Work: Rectification to footpath in HIG Layout

Tender Notification: EE/H/TEND/01/12-13 date: 11/04/2012
Item No: 12

Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clodsincluding loading & unloading, cost of labour Conveying the excavated earth to distance of upto 10kms including loading and unloading charges etc., complete as per specifications and direction of the Engineer-in-Charge.	170.10	Cum	165.00	Rupees One Hundred Sixty Five Only
2	Removing B.S. Slab drain and stacking, Refixing stone slabs of drains and pointing in C.M. (1:3) etc., complete as per specifications and direction of the Engineer-in-Charge.	119.60	Sqm	112.00	Rupees One Hundred Twelve Only
3	Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with lead upto 50m. and lift upto 1.5m. etc., complete as per specifications and direction of the Engineer-in-Charge.	16.75	Cum	1368.00	Rupees One Thousand Three Hundred Sixty Eight Only
4	Providing and laying heavy duty cobble stones 75mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick and bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries etc., complete as per specifications and direction of the Engineer-in-Charge.	80.00	Sqm	815.00	Rupees Eight Hundred Fifteen Only
5	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. 450 x 150 x 500mm etc., complete as per specifications and direction of the Engineer-in-Charge.	111.00	Nos	294.00	Rupees Two Hundred Ninety Four Only
6	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour etc., complete as per specifications and direction of the Engineer-in-Charge.	927.00	Sqm	51.00	Rupees Fifty One Only

Contractor

Executive Engineer (H)
Bruhat Bangalore Mahanagara Palike